Project: Maynilad- Ayala Alabang R1P ETAP Page: 1

Location: Ayala Alabang Muntinlupa 16.2.0C Date: 04-12-2019

Contract:

Engineer:

Revision:

Base

Filename: Study Case: LF

Study Case: LF

Config.: Normal

#### **Bus Loading Summary Report**

#### Directly Connected Load Total Bus Load

Bus			Constar	nt kVA	Cons	tant Z	Cons	stant I	Ger	neric				Percent
ID	kV	Rated Amp	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar	MVA	% PF	Amp	Loading
Bus1	34.500										0.570	78.8	9.5	
Bus2	0.480										0.546	80.9	685.6	
Bus3	0.480										0.544	81.0	685.6	
Bus5	0.480										0.544	81.0	685.6	
Bus6	0.480		0.236	0.214							0.544	81.0	685.6	
Bus7	0.460		0.109	0.048							0.119	91.5	144.7	
Bus8	0.460		0.109	0.048							0.119	91.5	145.0	
Bus9	0.460		0.109	0.048							0.119	91.5	152.3	
Bus10	0.460		0.010	0.006							0.011	86.5	14.1	
Bus11	0.460		0.010	0.006							0.011	86.5	14.2	
Bus13	0.460		0.010	0.006							0.011	86.5	14.2	
Bus14	0.480		0.002	0.002							0.003	81.0	3.3	
Bus15	0.240		0.002	0.002							0.003	81.5	7.6	
Bus16	0.460										0.120	91.6	144.7	
Bus17	0.460										0.121	91.6	145.0	
Bus19	0.460		0.048	0.029	0.012	0.007					0.070	85.0	88.1	

<sup>\*</sup> Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

<sup>#</sup> Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:	Maynilad- Ayala Alabang R1P	ETAP	Page:	2
Location:	Ayala Alabang Muntinlupa	16.2.0C	Date:	04-12-2019
Contract:			SN:	APSI-PH001
Engineer:		Study Case: LF	Revision:	Base
Filename:	Alabang R1P		Config.:	Normal

# **Branch Loading Summary Report**

CVT/P			11 6 D		Transformer				
CK1/1	CKT / Branch		Cable & Reactor			Loading (input)		Loading (output)	
ID	Туре	Ampacity (Amp)	Loading Amp	%	Capability (MVA)	MVA	%	MVA	%
Cable1	Cable	1003.37	685.58	68.33					
Cable3	Cable	1003.37	685.58	68.33					
* Cable10	Cable	76.20	88.15	115.68					
T1	Transformer				0.750	0.570	76.0	0.546	72.7
T2	Transformer				0.005	0.003	60.1	0.003	59.2

<sup>\*</sup> Indicates a branch with operating load exceeding the branch capability.

Project:	Maynilad- Ayala Alabang R1P	ETA	AP	Page:	3
Location:	Ayala Alabang Muntinlupa	16.2.0	0C	Date:	04-12-2019
Contract:				SN:	APSI-PH001
Engineer:		Study Cas	se: IF	Revision:	Base
Filename:	Alabang R1P	zaay cus	2	Config.:	Normal

# **Branch Losses Summary Report**

	From-To Bus Flow		To-From Bus Flow		Losses		% Bus Voltage		Vd % Drop	
Branch ID	MW	Mvar	MW	Mvar	kW	kvar	From	То	in Vmag	
Tl	0.449	0.351	-0.441	-0.321	7.7	30.4	100.0	95.7	4.29	
Cable1	0.441	0.321	-0.441	-0.319	0.9	1.2	95.7	95.5	0.24	
Cable3	0.441	0.319	-0.440	-0.319	0.1	0.1	95.5	95.4	0.02	
Cable6	0.111	0.048	-0.109	-0.048	1.7	0.3	95.4	98.2	1.33	
Cable7	0.010	0.006	-0.010	-0.006	0.1	0.0	95.4	99.0	0.55	
Cable8	0.010	0.006	-0.010	-0.006	0.1	0.0	95.4	98.9	0.64	
Cable9	0.010	0.006	-0.010	-0.006	0.1	0.0	95.4	98.8	0.73	
Cable10	0.059	0.037	-0.059	-0.037	0.1	0.0	95.4	99.5	0.14	
Cable 11	0.002	0.002	-0.002	-0.002	0.0	0.0	95.4	95.4	0.03	
T2	0.002	0.002	-0.002	-0.002	0.0	0.0	95.4	94.0	1.44	
Cable4	-0.109	-0.048	0.110	0.048	1.2	0.2	103.4	104.3	0.99	
Cable5	-0.109	-0.048	0.110	0.048	1.3	0.3	103.2	104.3	1.16	
					13.2	32.6				

**ETAP** Maynilad- Ayala Alabang R1P

Project:

16.2.0C Location: Ayala Alabang Muntinlupa Date: 04-12-2019

> SN: APSI-PH001

4

Page:

Contract: Engineer: Revision: Study Case: LF

Filename: Alabang R1P Config.: Normal

# **Alert Summary Report**

# % Alert Settings

	Critical	<u>Marginal</u>
<b>Loading</b>		
Bus	100.0	95.0
Cable	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
Generator Excitation		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

#### **Critical Report**

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus15	Bus	Under Voltage	0.240	kV	0.226	94.0	3-Phase
Cable10	Cable	Overload	76.202	Amp	88.15	115.7	3-Phase
VFD1	VFD	Overload	180.422	Amp	189.37	105.0	3-Phase
VFD2	VFD	Overload	180.422	Amp	189.71	105.1	3-Phase

# **Marginal Report**

Device ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus14	Bus	Under Voltage	0.480	kV	0.458	95.4	3-Phase
Bus2	Bus	Under Voltage	0.480	kV	0.46	95.7	3-Phase
Bus3	Bus	Under Voltage	0.480	kV	0.46	95.5	3-Phase
Bus5	Bus	Under Voltage	0.480	kV	0.46	95.5	3-Phase
Bus6	Bus	Under Voltage	0.480	kV	0.46	95.4	3-Phase

**ETAP** Maynilad- Ayala Alabang R1P 5 Project: Page: 16.2.0C Location: Ayala Alabang Muntinlupa Date: 04-12-2019 APSI-PH001 SN: Contract: Engineer: Revision: Study Case: LF Alabang R1P Config.:

# SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

Normal

	MW	Mvar	MVA	% PF
Source (Swing Buses):	0.449	0.351	0.570	78.79 Lagging
Source (Non-Swing Buses):	0.000	0.000	0.000	
Total Demand:	0.449	0.351	0.570	78.79 Lagging
Total Motor Load:	0.424	0.203	0.470	90.18 Lagging
Total Static Load:	0.012	0.007	0.014	85.00 Lagging
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	0.013	0.140		
System Mismatch:	0.000	0.000		

Number of Iterations: 3

Filename: